

# **ACS520 Reinstatement**

#### Contents

CS520	Reinstatement	1
ACS520.1	Scope	1
ACS520.2	2 General	1
ACS520.3	Parks and reserves	1

## ACS520.1 Scope

This section provides for reinstatement of all construction areas outside of highway corridors. The reinstatement of highway corridors shall be in accordance with the relevant Corridor Manager's requirements as appropriate.

#### ACS520.2 General

Unless otherwise specified in part or whole, all disturbed areas shall be restored to their original condition or better. Where the Works are in private land, the Contractor shall obtain the approval of the landowner for the reinstatement.

Final resurfacing shall not be carried out until the Contract Administrator is satisfied that the condition of the backfill is suitable. Permission to proceed with final resurfacing shall not relieve the Contractor of his maintenance responsibilities.

### ACS520.3 Parks and reserves

Reinstatement of grassed and planted areas outside of highway corridors shall comply with Auckland Council Standard Specification *ACS530 Planting*.